

Groveland Community Services District

18966 FERRETTI ROAD GROVELAND, CA 95321

PHONE (209)-962-7161 Ext. 18

FAX (209)-962-4943

Mary Laveroni Park Flood Restoration

Project Scope of Work:

1. Contractor hereby agrees to furnish all labor, materials, services, transportation, appliances, mechanical workmanship, transportation, communication, scaffolding, hoisting, supervision, coordination, permits, sales taxes, shop drawings and samples, to complete in a workman-like manner, the following work:
 - a. Remove all displaced soil and rock deposits as shown on the attached schematic, leveling the areas and placing/compacting the excess materials into eroded locations in the lower park site. Approximately 580 tons of displaced soil is to be redistributed on site.
 - b. Supply, install and compact 390 tons of road base or gravel in eroded areas shown on the attached schematic.
 - c. Regrade roadways, walkways for proper drainage and compact with 4" of gravel or road base
 - d. Install 160 feet of 1-inch PVC sch 40 water line from valve box to snack shack building
 - e. Install 140 feet of 2-inch PVC electrical conduit
 - f. Remove and replace existing damaged drinking fountain, installed with 3-foot by 3-foot reinforced concrete base (4-inch thickness) and 3 cubic foot gravel drain area below fountain
 - g. Remove old and pour new 1-cubic yard footings with 2-foot by 2-foot reinforced concrete base at grade for (3) canopy support poles on North Side of Amphitheater
 - h. Re-establish creek berm/bank by adding acceptable compacted fill material to an average height of 2-feet and a four foot base width
 - i. Fill and compact washed out drainage ditch and bank below upper park with material from the project site
 - j. Backfill 30" CMP behind Skate Park (next to Cal-Trans yard) with _____ cubic yards of 3-inch + riprap
 - k. Install, grade and compact 6-inches of sub base rock and 3-inches of hot mix asphalt surfacing per attached plans and specifications
 - l. Flush/clean 120-feet of 36" CMP.

Groveland Community Services District
Mary Laveroni Park Restoration Project

- m. Remove and re-install 75-feet of 4-inch PVC French drain with 1.5" drain rock
 - n. Properly dispose of all discarded asphalt, trash and rubbish and provide disposal receipts
- 2. Bid additive: Extend 12-inch culvert 130-feet from the upper park to the drainage ditch adjacent to the upper park fence
- 3. The District will provide the following:
 - a. Water for gravel compaction and dust control
 - b. Equipment staging area
 - c. Removal of the glass and small debris from the lawn area is hereby removed from the work scope

BIDDING REQUIREMENTS

- 1. Contractor shall provide a Payment Bond in the amount of 100% of the contract.
- 2. Contractor shall be required to enter into agreement with the District; see Attachment #1 to these specifications
- 3. Contractor shall complete work by August 30, 2018

BID SCHEDULE

UNIT PRICE LIST—FIGURES

WORK IDENTIFICATION _____

NAME OF BIDDER _____

BASE BID-SCHEDULE A					
Item No.	Item Description	Quantity	Unit	Unit Price in Figures	*Item Total Price in Figures
1	Equipment Mobilization	1	LS		
2	Clean up Displaced Spoils (rocks, sand, silt, asphalt) If material isn't used as fill it needs to be hauled to an approved landfill	App. 581	TN		
3	Remove and re-install French drain with 1.5" drain rock	App. 70	LF		
4	Backfill/grade/compact eroded areas of lower park	App. 392	TN		
5	Remove old and pour new footings for canopy support poles (3) on North side of Amphitheater				
6	Re-grade roadway's, walkway's, for proper drainage and compact with 4" of road base	App. 55,000	SF		
7	Fill and compact washed out drainage ditch & bank below upper Park	App. 70	LF		
8	Backfill 30" CMP with 4" Rip Rap behind Skate Park next to Cal-Trans yard	App. 140	TN		

SCHEDULE OF BID ITEMS - CONT.

9	Replace 1" Water line from valve box to Snack Shack	160	LF		
10	Remove and replace Drinking Fountain with concrete pedestal	1	LS		
11	Flush 36" CMP	800	LF		
12	Install 2-inch electrical conduit	140	LF		
13	Reestablish Creek berm	_____	LF		
14	Provide 6" rock sub base and hot mix asphalt surfacing, and parking lot striping as shown on the attached plans; attachment #2	_____	SF		
TOTAL BID – SCHEDULE A \$					

BASE BID TOTAL (Schedule A) (in writing) _____

ADDITIVE ALTERNATIVE – SCHEDULE B					
1B	Extend 12" Culvert from upper Park to lower to drainage ditch	130	LF		
TOTAL BID – SCHEDULE B \$					

BASE BID TOTAL (Schedule B) (in writing) _____

NOTE: Pursuant to Public Contract Code section 20103.8, the District will determine the lowest bid based on the total of the Base Bid (Schedule A)

The District has the option to reject all bids with or without cause. The District also has the option to remove bid items at its discretion. It is understood that the foregoing quantities are approximate only and are solely for the purpose of facilitating the comparison of bids, and that the contractor's compensation will be computed upon the basis of the actual quantities in the complete work, whether they be more or less than those shown.

ATTACHMENT # 3

Equipment staging area

